



[www.AmericanHermetics.net](http://www.AmericanHermetics.net)

To:

From: Mark Smith

[Mark@AmericanHermetics.net](mailto:Mark@AmericanHermetics.net)

1-800-240-9200

615-742-9222 fax

cc:

Date: Monday, February 20, 2012

# pages including cover: 1

### **Pre-Startup Check List**

To get full value out of our startup assistance, please make sure items below are completed before we arrive at jobsite:

1. Crankcase heater installed & operating within 24 hour
2. Contactors have been inspected / Prefer replaced with New
3. System has been leak checked
4. Condenser & Evaporator coils clean
5. Safeties checked and operable.
6. Put refrigerant in through the liquid line without starting compressor. You will be able to get about 70%-80% of charge in unit with a good vacuum.

\*\*\*\* Majority of items on attached startup sheet can be performed before we arrive.

Call if any questions